Legend

- Existing asphalt
- Existing vehicle access to shed
- Proposed grass
- Proposed planting
- Existing vegetation to be retained
- Existing tree to be retained
- Proposed trees
- Proposed fruit tree
- Wire archway *(refer to construction details)*
- Bench *(future community project)*
- Vegetable garden *(future community project)*
- Gravel Zen garden *(future community project)*
- Rocks *(relocated from onsite)*
- Lilydale toppings *(Note: The proposed 'farms' are a future community project')*
- Stepping stones *(relocated timber logs from onsite)*
- Moveable planters *(future community project)*

PLANT SCHEDULE

CODE	BOTANICAL NAME	COMMON NAME	HEIGHT X WIDTH*	POT SIZE	QTY
TREES					
A.pa.	Acer palmatum 'Sango Kaku'	Sango Kaku Maple	4x3m	300mm	2
B.pe.	Betula Pendula	Silver Birch	15x5m	45L/2m	9
C.a.	Cordyline australis	Cabbage Tree	10x 3m	330mm	7
E.Ls.	Eucalyptus 'Little Snowman'	Dwarf Snowgum	4x3-4m	400mm/1.2m	6
E.me.	Eucalyptus melliodora	Yellow Box	15-20x10-15m	45L/2m	4
E.ra.	Eucalyptus radiata	Narrow-leaf Peppermint	15-20x10-15m	45L/2m	3
L.in.	Lagerstroemia indica 'Yuma'	Yuma Crepe Myrtle	4x5-6m	45L/2m	3
L.tu.	Liriodendron tulipfera	Tulip Tree	15-20x12-15m	75L	1
L.st.	Liquidamber styraciflua	Liquid amber	15x8m	75L	6
M.pl.	Malus domestica 'Pink Lady'	Pink Lady Apple	4x4m	300mm	4
M.gs.	Malus domestica 'Granny Smith'	Granny Smith Apple	4x4m	300mm	4
M.rd.	Malus domestica "Red Delicious'	Red Delicious Apple	4x4m	300mm	5
O.eu.	Olea europaea 'europaea'	Olive Tree	8x4m	300mm	6
P.ad.	Prunus armeniaca 'Divinity'	Divinity Apricot	4x4m	300mm	2
P.as.	Prunus avium 'Starimson Cherry'	Starimson Cherry	4x4m	300mm	2
P.cm.	Prunus cerasus 'Morello Cherry'	Morello Cherry	4x4m	300mm	2
P.ca.	Pyrus calleryana 'Capital'	Upright pear	6x2.5-3.5m	45L/2m	9
P.cj.	Pyrus communis 'Josephine'	Josephine Pear	4x4m	300mm	1
P.cpt.	Pyrus communis 'Packham's Triumph Pear'	Packham's Triumphs Pear	4x4m	300mm	2
P.e.	Pittosporum eugenioides	Lemonwood	10x6m	400mm	1
P.t.	Pittosporum tenuifolium	Kohuhu	10x6m	400mm	1
T.l.	Tristaniopsis laurina	Kanooka	5.5x5-7m	45L/2m	1
U.p.	Ulmus parvifolia	Chinese Elm	7x7-8m	75L	2
Q.r.	Quercus robur	English Oak	11x11m	75L	2

5 0 5 10 15 20m

FENCELINE
EXISTING GYM
EXISTING COURT
EXISTING CRICKET NET
EXISTING FARM
OVAL
(reshaped)
EXISTING PLAYGROUND
AMERICAN GARDEN
EXISTING SHED
RELOCATED RAINWATER TANKS
ENGLISH GARDEN
FUTURE RELOCATABLE
RL. 233.5
PROPOSED LEARNING STUDIO
BUILDING 2
FFL. 235.5
BER
EXISTING STAFF
CARPARK
EXISTING
SHELTER
RELOCATED
PLAYGROUND
RELOCATABLE
RL. 233,5
PROPOSED LEARNING STUDIO
BUILDING 1
FFL. 235,5
PROPOSED ADMIN
WING
FFL. 239.79
COLONIAL SCHOOL HALL
REFURBISHMENT
FFL. 239.79
EXISTING ENTRY CANOPY
NEW ZEALAND
GARDEN
JAPANESE GARDEN
EXISTING TANK TO REMAIN
EXISTING SHED TO REMAIN
EXISTING SEATING
QUALE ROAD

© COPYRIGHT All rights reserved.
Beveridge Williams & CO Pty Ltd has granted a licence to the principal to use this document for its intended purpose.
No unauthorized copying is permitted.

Rev Description Date By App.

Rev Description Date By App.

Project Name: WANDIN YALLOCK PRIMARY SCHOOL

Drawing Title: LANDSCAPE PLAN - proposed trees

Client: peckvonhartel

Designed A.GUTHREY Date 30.11.10
Drawn A.GUTHREY
Approved J.GREEN Date 30.11.10
Sheet 01

Beveridge Williams
development & environment consultants
Suite 5/116 Hawthorn Road
Caulfield North VIC 3161
ph : 03 9528 4444
www.beveridgewilliams.com.au

Scale 1:300@A1
Project Ref. 1000065
Drawing No. 01
Rev. -
Drawing Ref. K:\JOBS DATA\1000065 WANDIN YALLOCK - SCHOOL_LAN\00\CAD\1000065 PP 20101130.DWG